

## Description of Alternatives

	Alternative 4		
Regulation Schedule	Deviation schedules for WCA 1, 2A, and 3A as specified by USACE.		
S-343 A/B and S-344	Closed Nov 1 to July 15 independent of WCA-3A levels.		
S-12 A/B/C/D	S-12A, B, C and D closed Nov 1 to Jul 15; Follow WCA 3A regulation schedule after Jul 15.		
S-333: G-3273 < 6.8'	S-333 open to deliver 55% of Shark Slough target flows as per rainfall plan target (rainfall formula + WCA 3A regulatory discharge).		
S-333: G-3273 > 6.8'	S-333 closed		
L-29 constraint	9.0 ft		
S-355A&B		Dry	Wet
	Open	8.50	8.50
	Close	6.50	6.50
S-337	Regulatory releases as per WCA-3A deviation schedule.		
S-151	Regulatory releases as per WCA-3A deviation schedule.		
S-334	Closed		
S-332B	Pumped up to <b>325 cfs</b> ; Dry    Wet On    4.5    4.5 Off    4.0    4.0		
S-332B Seepage Reservoir	160 acres with emergency overflow.		
S-332D	Pumped up to 500 cfs design capacity from Jul 16 to Nov 30; 325 cfs from Dec 1 to Jan 31; and 165 cfs from Feb 1 to Jul 15. Dry    Wet On    5.0    4.5 Off    4.8    4.0		
S-332	Closed		
S-175	Closed		
S-194	Operated to maximize flood control discharges to coast Dry    Wet Open    4.70    4.70 Close    4.20    4.20		
S-196	Operated to maximize flood control discharges to coast. Dry    Wet Open    4.70    4.70 Close    4.20    4.20		
S-176	Dry    Wet Open    5.00    5.00 Close    4.75    4.75		
S-18C	Dry    Wet Open    2.25    2.25 Close    2.00    2.00		